CHAPTER

General Information

The site preparation checklist at the end of this chapter helps ensure that all site preparations are completed before the delivery and installation of a VCO/4K system.

Installation Planning

Installation planning includes:

- · Location
- Environment
- · Power
- Alarms
- · Operating limits for cards and peripherals

Review Chapter 2, "Installation Planning," and complete all modifications to the installation site before the arrival of the VCO/4K. For additional information on installation planning, refer to Appendix A, "System Component Weights."

Cabling Preparations

Cabling preparation includes:

- · Digital interconnections
- Cabling to a VCO/4K system

This guide does not describe how to construct and wire cables. Review the "Digital Interconnections" section on page 2-8 before prewiring the installation site.

Regulatory Considerations

Refer to the "Federal Communication Commission (FCC) Information" section on page 2-9.

Peripheral Equipment

Every VCO/4K system requires connection to a video display terminal (VDT) and dot matrix printer for system administration purposes. A remote maintenance modem is also an option. Topics discussed include:

- · Types of peripheral equipment
- · Installation planning for peripheral equipment
- · Peripheral cabling
- · Routing peripheral equipment through transfer switches

Host Communication Links

VCO systems communicate with a host computer system over Ethernet links. This is discussed in Chapter 4, "Host Communication Cabling." For detailed information on using the optional Ethernet communications package for the VCO/4K, refer to the *Cisco VCO/4K Ethernet Guide*.

Site Preparation Checklist

If you request Cisco to perform the VCO/4K installation and system certification, you must complete the following checklist before Cisco personnel arrive:	
1.	Verify the space requirements, including access and passageways to the equipment room for the VCO/4K system and the associated peripheral equipment (Chapter 2, "Installation Planning").
2.	Complete all modifications to the installation site, including electrical service and HVAC modifications (Chapter 2, "Installation Planning").
3.	$\underline{\hspace{0.3cm}}$ Construct, label, and properly route cables to the VCO/4K location (Chapter 2, "Installation Planning").
4.	Order telco facilities (subscriber loops, trunks, T-spans, and so forth); coordinate their installation, and test all facilities following installation (<i>Cisco VCO/4K Hardware Planning Guide</i>).
5.	Install the DC Power Plant (if required) and terminate the feeder circuits near the VCO/4K (Chapter 2, "Installation Planning").
6.	Install the earth ground so you can terminate it at the power entry module on the $VCO/4K$ (Chapter 2, "Installation Planning").
7.	Connect the EIA/TIA-232 and parallel cables from the VCO/4K to the peripheral equipment (console, printer, modem, and switches). (See Chapter 3, "Peripheral Equipment.")
8.	Install the business line for the remote maintenance modem. Terminate the line near the installation location for the modem (optional). (See Chapter 3, "Peripheral Equipment.")
9.	Connect the Ethernet transceiver and cables for use as the host communication links between the host computer and the VCO/4K (Ethernet Communications Package). (See Chapter 4, "Host Communication Cabling.")
10.	Install and test the host computer system.
11.	Install an AC branch circuit, either 120V, 50/60 Hz, 3A or 240V, 50/60 Hz, 15A, (if required) near the VCO/4K location for connection to the power supply (Chapter 2, "Installation Planning").

12. ____ Install the 120V, 50/60 Hz, 20A AC branch circuit (if required) to power the peripheral equipment (may require more than one outlet). (See Chapter 3, "Peripheral Equipment.")

Site Preparation Checklist